

KEY MAP

## DRAWING INDEX

DRAWING No.	REV. No.	<u>DATE</u>	<u>DESCRIPTION</u>
000	0	JUN 2021	COVER SHEET
001	О	JUN 2021	QUATERNAY WATERSHED
002	0	JUN 2021	WATERSHED PLAN
003	0	JUN 2021	PRE-DEVELOPMENT PLAN
004	0	JUN 2021	POST-DEVELOPMENT PLAN
005	0	JUN 2021	GRADING PLAN
006	0	JUN 2021	ROAD CROSS-SECTIONS
007	0	JUN 2021	ROAD PROFILE
800	0	JUN 2021	SEDIMENT CONTROL PLAN
009	0	JUN 2021	SEDIMENT CONTROL DETAILS
010	0	JUN 2021	MUD-MAT & CHECKDAM PLAN & DETAILS
011	0	JUN 2021	POND CROSS-SECTION

## RIVERVIEW HEIGHTS PHASE II Draft plan no. 23T-98003


CAMELOT AT MINTO
PART OF LOT 18 & 19, CONCESSION 12


## TOWNSHIP OF MAPLETON COUNTY OF WELLINGTON

## STORMWATER MANAGEMENT PLAN



282 NEAL DR., RICHM, OND HILL, ONT, L4C 3L4








RIVERVIEW HEIGHTS — PHASE 2 DRAYTON, ONTARIO

RED-LINED DRAFT PLAN NO. 23T-98003

QUATERNAY WATERSHED










> RIVERVIEW HEIGHTS — PHASE 2 DRAYTON, ONTARIO


> RED-LINED DRAFT PLAN NO. 23T-98003


WATERSHED PLAN



















- 1.) ALL SILT FENCING TO BE INSTALLED PRIOR TO COMMENCEMENT OF ANY AREA GRADING, EXCAVATION, OR DEMOLITION.
- 2.) EROSION CONTROL FENCING TO BE PLACED AROUND THE BASE OF ALL STOCKPILES. ALL STOCKPILES TO BE KEPT A MINIMUM 2.5m FROM ALL PROPERTY LINES.
- 3.) ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED AS SITE DEVELOPMENT PROGRESSES. CONTRACTOR PROVIDE ALL ADDITIONAL EROSION CONTROL STRUCTURES.
- 4.) EROSION CONTROL STRUCTURES TO BE MONITORED REGULARLY BY CONESTOGA—ROVERS & ASSOCIATES LTD. AND ANY DAMAGE REPAIRED IMMEDIATELY. SEDIMENTS TO BE REMOVED WHEN ACCUMULATIONS REACH A MAXIMUM ½ THE HEIGHT OF THE SILT FENCE.
- 5.) ALL EROSION CONTROL STRUCTURES TO REMAIN IN PLACE UNTIL ALL DISTURBED GROUND SURFACES HAVE BEEN RE-STABILIZED. ALL DISTURBED AREAS AND STOCKPILES NOT UNDER ACTIVE CONSTRUCTION, OR PROPOSED TO BE WITHIN 6 MONTHS, ARE TO BE STABILIZED WITH TOPSOIL AND SEED.
- 6.) NO ALTERNATE METHODS OF EROSION CONTROL PROTECTION SHALL BE PERMITTED UNLESS APPROVED BY CONESTOGA—ROVERS & ASSOCIATES LTD.
- 7.) CONTRACTOR RESPONSIBLE FOR REMOVING SEDIMENTS FROM THE MUNICIPAL ROADWAYS AT THE END OF EACH WORK DAY.
- MUD MATS TO BE PROVIDED ON ALL SITE LOCATIONS WHERE CONSTRUCTION VEHICLES EXIT THE SITE. MUD MATS SHALL BE A MINIMUM OF 6.0m WIDE, 15.0m LONG (LENGTH MAY VARY DEPENDING ON SITE LAYOUT) AND 0.3m DEEP AND SHALL CONSIST OF 200mm CLEARSTONE MATERIAL OR APPROVED EQUIVALENT. CONTRACTOR TO ENSURE ALL VEHICLES LEAVE THE SITE VIA THE MUD MAT AND THAT THE MAT IS MAINTAINED AND A MANNER TO MAXIMIZE IT'S EFFECTIVENESS AT ALL TIMES.
- 9.) CONESTOGA—ROVERS & ASSOCIATES LTD. TO MONITOR THE SITE DEVELOPMENT TO ENSURE ALL EROSION CONTROLS ARE INSTALLED AND MAINTAINED TO CITY REQUIREMENTS. CONTRACTOR TO COMPLY WITH THE ENGINEER'S INSTRUCTIONS TO INSTALL, MODIFY, OR MAINTAIN EROSION CONTROL WORKS.
- 10.) IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR HIS/HER REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, HE/SHE MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF

CONSENT MUST BE SUBMITTED TO THE DEPARTMENT OF PUBLIC WORKS—ENGINEERING DEVELOPMENT DIVISION, PRIOR TO ANY WORK BEING PROFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THIS PROPERTY OWNERS OWN RISK.



SILT FENCE C/W
PAIGE WIRE DETAIL
N.T.S.




SEDIMENT CONTROL DETAILS


18983-00

**ABEC** 


N.T.S


282 NEAL DR. HMOND HILL, ON L4C 3L4











RIVERVIEW HEIGHTS - PHASE 2 DRAYTON, ONTARIO

RED-LINED DRAFT PLAN NO. 23T-98003

POND CROSS-SECTION

